CALDERBANK VINE

Chartered Building Surveyors · Manchester · Leeds · Birmingham

BUILDING SURVEY REPORT

Calderdale House, 14–18 Sefton Street, Manchester M3 4AP

Instructed by: Ellwood Estates Partners Limited · Report ref CBV-2025-0312 · Inspection date: 19 February 2025

1. Instructions and scope

Calderbank Vine was instructed by Ellwood Estates Partners Limited to carry out a pre-acquisition building survey of Calderdale House, a four-storey purpose-built office building of approximately 31,400 sq ft NIA constructed in 1998 and refurbished in 2017. This report covers the condition of the structure, building fabric, roof, mechanical and electrical services and external areas. It does not constitute a measured survey or a valuation.

2. Construction and general condition

The building is of steel-framed construction with reinforced concrete floors, a brick and curtain-walling external envelope and a flat roof with single-ply membrane covering. Overall the building is in good condition commensurate with its age and the 2017 refurbishment. We identified no evidence of structural movement, settlement or significant defects to the frame or floors.

3. Element-by-element assessment

Element	Condition	Priority	Indicative cost
Structural frame & floors	Good — no movement observed	None	—
Roof (single-ply membrane)	Fair — membrane approx. 8 yrs old; localised ponding at NE corner	Medium (monitor)	£6,000–£9,000 (5-yr)
External envelope / curtain walling	Good — sealant renewal advisable to W elevation	Low	£4,500
Windows	Good — double-glazed units, 2017	None	—
Passenger lift (single, 1998)	Poor/fair — overdue major overhaul; controller obsolete	High	£22,000–£26,000
Heating / cooling (VRF, 2017)	Good — within service life	None	—
Electrical installation	Good — EICR satisfactory (2023)	None	—
Car park (lower ground)	Fair — surfacing tired; drainage gully to clear	Low	£3,000

4. Principal findings

- Passenger lift: the single passenger lift dates from the original 1998 construction and is overdue a major overhaul; the controller is obsolete. We recommend budgeting £22,000–£26,000 for an overhaul within the next 12 months. This is the most significant item in the report.
- Flat roof: the single-ply membrane is approximately eight years old and in fair condition, with localised ponding at the north-east corner. No immediate leak risk; we recommend monitoring and budgeting for partial recovering within five years.
- External sealants: renewal of perimeter sealant to the west elevation curtain walling is advisable within 12 months (£4,500).

5. Environmental and statutory

An asbestos management survey dated 2017 is in place; no asbestos-containing materials requiring removal were identified. The building has a valid EPC rating of C. We saw no evidence of damp or timber decay. The building appears to comply with current fire-safety requirements for a building of this type, subject to the managing agent's fire risk assessment, a copy of which should be obtained.

6. Conclusion

Calderdale House is a well-located and generally well-maintained office investment. Subject to addressing the passenger lift overhaul and the routine roof and sealant items identified above, the building is suitable for acquisition. The aggregate of the high- and medium-priority items is in the order of £30,000–£40,000 over the next five years, the bulk of which (the lift) is in principle recoverable through the service charge.